

La calandra MC19 viene installata al termine di una linea di accoppiatura MC2001/MESL - MC2000/MESL.
 The MC19 calender is installed at the end of the MC2001/MESL – MC2000/MESL laminator line.

SPESSORE E LARGHEZZA MASSIMI DELL'ACCOPIATO DA CALANDRARE	S_{max}	6 mm ⁽¹⁾	15/64" ⁽¹⁾
	W_{max}	740 mm ⁽¹⁾	29 1/8" ⁽¹⁾
VELOCITA' DI PRODUZIONE FINO A: SPEED UP TO:		52 cicli/min ⁽¹⁾	52 cycles/min ⁽¹⁾
POTENZA ISTALLATA ELECTRICAL POWER		1.1 kW	1,5 hp
PESO NET WEIGHT		250 kg	550 lb

- (1) La velocità di produzione massima ed i limiti di prodotto raggiungibili dipendono da diversi fattori tra cui: la tipologia e le caratteristiche dei materiali usati (carta, cartone e collante), la formazione del personale addetto ed il formato del prodotto in lavorazione.
 The maximum production speed and the reachable product limits depend upon various factor including: the type and specifications of the materials used (paper, cardboard and glue), personnel training and size of the product being processed.

Le caratteristiche possono essere modificate senza preavviso.
 Technical specifications are subject to change without prior notice.

MC19
Vista della calandra / Picture of the calender



MC19
Layout e Ingomri
Layout and Overall Dimensions

